

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42443

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

Name of Work: Maintenance of Crematorium Burial ground and office maintenance in ward no 11 (Kuvempunagara)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MURTHY K G (ARM CONSTRUCTIONS)	
				In Figures	In Words
1	30.6	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	250.22	Rupees Two Hundred Fifty and Twenty Two Paise Only
2	64	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	300.46	Rupees Three Hundred and Forty Six Paise Only
3	9.6	Providing and laying Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days etc complete as per specifications and directions of engineer in charge of the work	Cum	5139.96	Rupees Five Thousand One Hundred Thirty Nine and Ninety Six Paise Only
4	17.28	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6 stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4618.43	Rupees Four Thousand Six Hundred Eighteen and Forty Three Paise Only
5	12.96	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5509.76	Rupees Five Thousand Five Hundred Nine and Seventy Six Paise Only
6	76.8	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	97.47	Rupees Ninety Seven and Forty Seven Paise Only
7	2.88	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5308.78	Rupees Five Thousand Three Hundred Eight and Seventy Eight Paise Only
8	96	Providing and constructing road bearing wall with solid concrete blocks of size 400x150x200 mm having block density not less than 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	946.03	Rupees Nine Hundred Forty Six and Three Paise Only
9	204.8	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	202.72	Rupees Two Hundred Two and Seventy Two Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MURTHY K G (ARM CONSTRUCTIONS)	
				In Figures	In Words
10	204.8	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer etc complete as per specifications and directions of engineer in charge of the work	Sqm	102.5	Rupees One Hundred Two and Fifty Paise Only
11	6.3	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc complete as per specifications and directions of engineer in charge of the work	Sqm	3026.7	Rupees Three Thousand Twenty Six and Seventy Paise Only

Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92